
MORMON TREK BOULEVARD



Safety Improvements from Melrose Ave to Iowa Hwy 1






Project Team

- City of Iowa City
 - Jason Havel, P.E. City Engineer
 - Scott Sovers, P.E. Project Manager
 - Kent Ralston, AICP Transportation Planner
 - Darian Nagle-Gamm, AICP Transportation Planner
- Snyder & Associates, Inc.
 - Brenna Fall, P.E. Project Manager
 - Dax Suntken, E.I. Project Engineer
 - Justin Jackson, P.E. Traffic Engineer
 - Rich Voelker, P.E. Transportation Group Director






Lane Reconfiguration








Increased Sight Distance








Reduced Conflict Points










Reduced Conflict Points








Annual Average Daily Traffic

Roadway Segment	2002	2006	2010	2014	MPOJC Model 2010	MPOJC Model 2040
Melrose Ave, south of	16,900	-	14,100	_	14,100	14,300
Rohret Rd, north of	-	15,400	-	8,800	15,400	19,980
Rohret Rd, south of	10,900	-	10,300	-	10,300	13,800
lowa Hwy 1, north of	12,200	9,800	12,100	13,300	12,100	14,900

- DOT did not count at this location during count year







Crash History

Petsel Pl to West Side Dr

- 126 Crashes
- Injuries
 - 1 Major
 - 19 Minor
 - 28 Possible/Unknown
- \$645,100 in Property Damage Reported
- 30 Followed Too Close
- 26 FTYROW Left Turn / Driveway



Crash Reduction



Following too close

Failing to yield the right of way







SNYDER & ASSOCIATES Engineers and Planners

Funding

- Traffic Safety Improvement Program (TSIP)
- Comes from Iowa Road Use Tax Fund
- Applied for in 2014 and granted full request of \$500,000
- Calculated Benefit to Cost Ratio of 1.5:1
- 25% Reduction in Crashes Expected





Travel Time Study

Existing Condition

- 4 Lanes (2 each direction)
- Measured AverageTravel Time = 281 sec

Travel Time Increase of approximately 30 seconds over the entire corridor

Proposed Condition

- 3 Lanes (1 each direction w/ continuous TWLTL)
- Protected/Permissive left turn phasing
- Updated signal coordination plan
- Travel Time = 305 sec*
 - * Traffic Model Analysis Derived





Level of Service (LOS)

Definition: Quality measure describing operational traffic conditions, in terms of speed, travel time, freedom to maneuver, traffic interruptions, comfort, and convenience.

Six Levels used to evaluate a corridor

- LOS A to LOS F
 - LOS A = Best Operating Conditions (free-flow)
 - LOS F = Worst Operating Conditions (congested)
- LOS C and LOS D
 - Considered acceptable operating service for design and planning





Level of Service (LOS)

Intersection	Current Traffic 4-Lane	Current Traffic 3-Lane	Future Traffic 4-Lane	Future Traffic 3-Lane
Melrose Ave	С	С	С	С
Cameron Way	Α	Α	Α	Α
Benton St	Α	В	В	В
Rohret Rd	Α	С	В	С
Westside Dr	Α	В	В	В

Average LOS based on calculated delay at all legs of the intersection during the AM Peak Hour.





Level of Service (LOS)

Intersection	Current Traffic 4-Lane	Current Traffic 3-Lane	Future Traffic 4-Lane	Future Traffic 3-Lane
Melrose Ave	С	С	С	С
Cameron Way	Α	Α	Α	В
Benton St	В	Α	В	В
Rohret Rd	Α	С	Α	С
Westside Dr	Α	В	В	В

Average LOS based on calculated delay at all legs of the intersection during the PM Peak Hour.





Project Specifics

- Lane reconfiguration proposed from Melrose Ave to north of Westside Dr
 - 11' wide Through Lanes
 - 12' wide Continuous Two-Way-Left-Turn Lane
 - Dedicated Bike Lanes
- Addition of a dedicatedRight Turn Lane at Benton St







Project Specifics

- ADA Sidewalk Ramp Reconstruction
- Traffic SignalImprovements
 - Coordinated signal timing
 - Protected/permissive left-turn phasing
- Pavement patching



SNYDER & ASSOCIATES

Engineers and Planners



THANK YOU FOR COMING

Please provide us with your comments.

Comment forms are available at the registration table or you may email the project team at bfall@snyder-associates.com.



